

# BGC Concrete Mobile Batching Plant



## **BGC Concrete operate Portabatch 2000 mobile plants providing a flexible, quickly established batching facility for remote area works.**

This popular plant type is in use throughout Australia, has a maximum output capacity of 50m<sup>3</sup> /hr, suitable for most remote area works. Agitator trucks are available to match plant output and on site location.

The plants are registered with the Department of Environment satisfying current environmental guidelines.

Mobile in the true sense of the word they can be relocated at short notice, producing concrete within a few hours, requiring only a loader, raw materials and a supply of water to allow production to commence.

Capable of producing mixes to Australian Standard -AS1379, materials are weighed on load cells, water and admixtures measured through flow meters, batched and recorded. A 50 tonne cement silo, water and two admixtures tanks are integral to the plant, additional cement silos, tanks and chillers are available on request to suit individual project and mix requirements.

Trained personnel are on hand to ensure that projects are completed in a timely, professional manner whilst concentrating upon safe work practices, quality assurance and the environment.

**All enquiries please call  
BGC Concrete on (08) 9261 1899**

